



Authorization for Pole Attachment Make Ready Work

Licensee

DataLink, Ltd.

The enclosed Pole Attachment Make-Ready Work Costs Estimate Forms provide the total estimated Make-Ready Costs for your Pole Attachment Application Number P.A. _____, dated _____, 2014.

Should you desire for DataLink to complete this Make-Ready Work, please complete the Authorization for Make-Ready Work section of this form and return it along with an advance payment in the amount of \$ _____. Please make check payable to DataLink and mail it to the address below.

_____ No Make-Ready work Required

Authorized DataLink Representative

Date

Authorization for Make-Ready Work

_____ Attached is a check in the amount of \$ _____ for the above referenced Make-Ready Work.

_____ Please bill me for the above Make Ready Work.

DataLink is authorized to proceed with the Make-Ready work described above in accordance with the License Agreement.

Authorized Licensee Representative

Date

Date Make-Ready Work Completed

DataLink Work Order Number



DATALINK MAKE READY ESTIMATE – Moxam Road

Work Order: **WF0436766**

Item	Qty	Total Estimate	Total Actual
40' WOOD POLE	2	587.84	
35' WOOD POLE	2	442.33	
Anchor – Screw 10" Helix	4	217.32	
Guy – overhead guy	1	53.14	
G1 – Down Guy	9	448.87	
Single Phase – Tangent	2	143.88	
Single Phase – Dead End	1	52.16	
Secondary Straight Thru	1	11.22	
Secondary – Dead End 2/0	1	24.54	
Service Connection 2/0 tr	400	713.24	
Total Material		2,694.53	
Raising of Weatherheads	6	7,200.00	
Labour		3,201.52	
Equipment		1,953.88	
Total Estimate		15,049.93	



DATALINK MAKE READY DETAIL

Work Order: WF0436766

Location: Moxam Road

Poles impacted:

Pole #	Location
35375	Moxam Road
29481	Moxam Road
35233	Moxam Road
28194	Moxam Road
29482	Moxam Road
30723	Moxam Road
30678	Moxam Road
30677	Moxam Road
32383	Moxam Road
36967	Moxam Road
3073	Moxam Road
37379	Moxam Road
3354	Moxam Road
44278	Moxam Road
44279	Moxam Road
44280	Moxam Road

Items to be actioned	Units	Pole #
New Poles	3	44278, 44279, 44280
Anchors	4	44280, 35233, 42033 (2)
Pole Top Extension	2	29482, 37379
Attach Primary	1	44278
Attach Secondary	1	44278
Attach Neutral	1	44278
Remove Secondaries	2	30723, 30677
Remove Transformer	1	3354
Relocate Prim & Neutral Lines	2	3354, 42033
Install Triplex 2/0	2	30723, 30677
Install Down Guys	4	35233, 30723, 30678, 30677
Raise Weatherheads	6	35375 (2), 35233, 3354, 30723 (2)

